
August 15, 2018

Mathew Sam
Detroit Public Schools
1601 Farnsworth
Detroit, Michigan 48202

SUBMITTED VIA EMAIL TO: mathew.sam@detroitk12.org

**SUBJECT: Drinking Water Screening Report
 Amelia Earhart Elementary/ Middle School
 1000 Scotten
 Detroit, Michigan**

Dear Mr. Sam:

ATC Group Services, LLC (ATC) is pleased to submit this Drinking Water Screening Report for the subject school. The drinking water samples collected from the school were submitted to Pace Analytical Services, LLC, for Michigan Department of Environmental Quality (MDEQ) Drinking Water Certified lead and copper analysis.

SCOPE OF WORK

At the request of the Detroit Public Schools (DPS), ATC collected drinking water samples as a general screening for copper and lead at the subject school. The water sampling conducted included the sampling of fixtures within teacher's lounges, kitchens, water fountains and pre-k classrooms. One (1) sample was collected at each outlet: a first draw (Primary) sample. The Primary samples were collected from outlets that had been inactive for a minimum of eight to eighteen hours. The fixture inventory locations including the sample locations are shown on the Fixture Inventory Locations Map included under Attachment A and fixture inventory photos including the sample location photos are included in a Fixture Inventory Photo Log under Attachment B.

The drinking water samples were collected in 125 milliliter, wide-mouth sample containers, containing nitric acid (preservative). Each sample container was labeled utilizing a unique coding system that identified: the type of drinking outlet sampled as well as the location.



ENVIRONMENTAL • GEOTECHNICAL
BUILDING SCIENCES • MATERIALS TESTING

46555 Humboldt Drive
Novi, Michigan 48377
Telephone 248-669-5140
www.atcgroupservices.com

The samples were transported under chain of custody to Pace Analytical Services, LLC, located at 5560 Corporate Exchange Ct. SE Grand Rapids, MI for MDEQ drinking water certified lead and copper analysis, using analytical method EPA 200.8 rev 5.4.

FINDINGS

Analytical results indicate that none of the samples analyzed were above the EPA recommended limits of 15 micrograms per liter (ug/L) for lead. None of the samples analyzed were above the EPA recommended limits of 1300 micrograms per liter (ug/L) for copper. The table below summarizes the analytical results for the samples submitted. The laboratory analytical reports and chain of custody are provided in Attachment C.

Table 1 – Water Testing Results (August 13, 2018)

Sample Number	Location	Description	Total Lead (ug/l)	Total Copper (ug/l)
1-Hall@office-DWF-8	Hall near the office	Drinking water fountain - left	<1.0 ug/L	205 ug/L
1-Hall@office-DWF-9	Hall near the office	Drinking water fountain - left	<1.0 ug/L	218 ug/L
1-Kitchen-KF-3	Kitchen - east wall	3 chamber sink, left	<1.0 ug/L	241 ug/L
1-Kitchen-KF-5	Kitchen - east wall	3 chamber sink, right	<1.0 ug/L	312 ug/L
1-Kitchen-KF-6	Kitchen - east wall	Kitchen faucet - dish washing sink	<1.0 ug/L	266 ug/L
1-Hall@door22-DWF-10	Hall next to door #22	Drinking water fountain - left	<1.0 ug/L	279 ug/L
1-Hall@door22-DWF-11	Hall next to door #22	Drinking water fountain - right	<1.0 ug/L	268 ug/L
1-Hall@C109-DWF-13	Hall next to C109	Drinking water fountain - right	<1.0 ug/L	465 ug/L



ENVIRONMENTAL • GEOTECHNICAL
BUILDING SCIENCES • MATERIALS TESTING

46555 Humboldt Drive
Novi, Michigan 48377
Telephone 248-669-5140
www.atcgroupservices.com

Sample Number	Location	Description	Total Lead (ug/l)	Total Copper (ug/l)
1-Hall@C209-DWF-14	Hall next to C209	Drinking water fountain - left	1.9 ug/L	514 ug/L
1-Hall@C209-DWF-15	Hall next to C209	Drinking water fountain - right	2.2 ug/L	496 ug/L
1-B120-KF-16	In room B120 (teacher's lounge)	Kitchen faucet	<1.0 ug/L	455 ug/L
1-A103-CF-17	In room A103 (headstart)	Classroom faucet with bubbler	<1.0 ug/L	247 ug/L
1-A106-CF-18	In room A106 (headstart)	Classroom faucet with bubbler	<1.0 ug/L	254 ug/L
1-A108-CF-19	In room A108 (headstart)	Classroom faucet with bubbler	1.1 ug/L	355 ug/L
1-Hall@A119-DWF-20	In hall across from room A119	Drinking water fountain - left	<1.0 ug/L	228 ug/L
1-Hall@A119-DWF-21	In hall across from room A119	Drinking water fountain - right	<1.0 ug/L	213 ug/L
1-A119-KF-22	In room A119 (cafeteria)	Kitchen faucet	<1.0 ug/L	255 ug/L
2-Hall@A217-DWF-26	In hall across from room A217	Drinking water fountain - left	<1.0 ug/L	246 ug/L
2-Hall@A217-DWF-27	In hall across from room A217	Drinking water fountain - right	<1.0 ug/L	217 ug/L
2-A217-KF-28	In room A217 Cafeteria	Kitchen faucet	<1.0 ug/L	210 ug/L

Key: NA - Not Analyzed

ug/L- micrograms per liter /parts per billion (ppb)

Analysis of samples in the building did not exceed the MCL for either lead or copper. See recommendations below.

RECOMMENDATIONS

For drinking water fixtures that exceed the MCL after the initial sampling, ATC recommends the following:

1. Implement a plan in accordance with MDEQ Guidance on Drinking Water Sampling for Lead and Copper, April, 2016 Version2; OR
2. Remove fixture from service.
3. Implement a flush plan for fixtures that exceed the MCL of the initial sample according to MDEQ Guidance and the EPA's 3T's for Reducing Lead in Drinking Water in Schools.


LIMITATIONS

The sampling and analysis completed was: a preliminary screening for lead and copper only, to assess lead and copper concentrations (ug/L) at drinking water outlets in the school designated as high use by DPS, and may not be representative of all drinking water outlets within the school. If lead or copper concentrations were identified above their respective MCL's at any of the drinking water outlets tested, further review of the plumbing system, fixtures affected, and testing may be completed to assess the source of the elevated levels of lead and/or copper, as well as, any other response actions deemed necessary by DPS.

Future drinking water evaluation and sampling in accordance with the recommendations may be predicated on applicable guidelines by the MDEQ or EPA and will be determined prior to developing a sampling plan for the school.

Sincerely,

ATC Group Services, LLC



Martin K. Gamble
Senior Project Manager



Robert C. Smith
Building Science Department Manager

Attachments

Attachment A: Fixture Inventory Locations Map/Form

Attachment B: Fixture Inventory Photo Log

Attachment C: Laboratory Analytical Report