



August 1, 2016

Debra Spring Matrix Head Start 2051 Rosa Parks Boulevard Detroit, Michigan 48216

SUBMITTED VIA EMAIL TO: dspring@matrix.org

**SUBJECT:** Drinking Water Screening Report

**Blessed Beginnings Learning** 

13828 Eastburn Street Detroit, Michigan 48205

Dear Ms. Spring:

ATC Group Services, LLC (ATC) is pleased to submit this Drinking Water Screening Report for the subject school. The drinking water samples collected from the school were submitted to TriMatrix Laboratories, for Michigan Department of Environmental Quality (MDEQ) Drinking Water Certified lead analysis.

### **SCOPE OF WORK**

At the request of the Matrix Head Start (Matrix), ATC collected drinking water samples as a general screening for lead at the subject school. Matrix in coordination with the City of Detroit Health Department determined that the screening would consist of collection of water samples from three (3) high priority water outlets (drinking fountains, kitchen/food preparation area faucets, etc.), regularly used by students and staff for drinking, as designated by Matrix personnel. Two (2) samples were collected at each outlet: a first draw (Primary) sample; and a Flush sample. The Primary samples were collected from outlets that had been inactive for a minimum of eight hours. The Flush samples were collected after the water was allowed to run for a minimum of thirty (30) seconds at each of the sample locations.

The drinking water samples were collected in 125 milliliter, wide-mouth sample containers, containing nitric acid (preservative). Each sample container was labeled utilizing a coding system that identified: the type of drinking outlet sampled, Drinking Water Fountain (DWF), Drinking Water Cooler (DWC), Kitchen Faucet (KF) etc.; and a (P) for primary samples and a (F) for flush samples.





The samples were transported under chain of custody to TriMatrix Laboratories, located at 5560 Corporate Exchange Court SE, Grand Rapids Michigan for MDEQ drinking water certified lead analysis, using analytical method EPA 200.8 rev 5.4.

As per the EPA's 3T's for Reducing Lead in Drinking Water in Schools, Revised Technical Guidance (October 2006) analysis of the flush sample(s) was only performed if analysis of the first draw (Primary) sample(s) indicated lead and/or copper concentrations greater than the EPA established Maximum Contaminate Level (MCL).

### **FINDINGS**

Analytical results indicate that none of the samples analyzed were above the EPA recommended limits of 0.015 milligrams per liter (mg/L) for lead. The table below summarizes the analytical results for the samples submitted. The laboratory analytical reports and chain of custody are provided in Attachment A.

Sample Number	Total Lead (Drinking Water)	MCL
1-BS-P-BB (Bathroom Sink-Basement)	<0.0010 mg/L	0.015 mg/L
1-BS-F-BB (Bathroom Sink-Basement)	NA	0.015 mg/L
2-KS-P-BB (Kitchen Sink-Basement)	<0.0010 mg/L	0.015 mg/L
2-KS-F-BB (Kitchen Sink-Basement)	NA	0.015 mg/L
3-US-P-BB (Utility Sink-Basement)	0.0088 mg/L	0.015 mg/L
3-US-F-BB (Utility Sink-Basement)	NA	0.015 mg/L

Key: NA - Not Analyzed

mg/L- milligrams per liter /parts per million (ppm)



46555 Humboldt Drive Novi, Michigan 48377 Telephone 248-669-5140 www.atcgroupservices.com

### **LIMITATIONS**

The sampling and analysis completed was: a preliminary screening for lead only, to assess lead concentrations (mg/L) at drinking water outlets in the school designated as high use by Matrix, and may not be representative of all drinking water outlets within the school. If lead concentrations are identified above their respective MCL's at any of the drinking water outlets tested, further review of the plumping system, fixtures affected, and testing should be completed to assess the source of the elevated levels of lead, as well as, any other response actions deemed necessary by Matrix.

The drinking water screening proposed and conducted by ATC was devised in cooperation with Matrix, City of Detroit Health Department and utilizing the EPA's 3Ts for Reducing Lead in Drinking Water in Schools and may not meet all of the recommendations provided by the MDEQ "Guidance on Drinking Water Sampling for Lead and Copper at Schools and Daycares on Community Water Supplies" Version 2.0 - April 13, 2016. Future drinking water evaluation and sampling in accordance with the recommendations may be predicated on applicable guidelines by the MDEQ or EPA and will be determined prior to developing a sampling plan for the school.

Sincerely,

**ATC Group Services, LLC** 

Marte & Somble

Martin Gamble

Senior Project Manager

Robert C. Smith

**Building Science Department Manager** 

Robert C. Kiniz

# APPENDIX A LABORATORY ANALYTICAL REPORT



July 15, 2016

**ATC Group Services** Attn: Mr. Robert Smith 46555 Humboldt, Suite 100 Novi, MI 48377

### **Project: School Drinking Water Testing**

Dear Mr. Robert Smith,

Enclosed is a copy of the laboratory report for the following work order(s) received by TriMatrix Laboratories:

Work Order	Received	Description
1607021	06/30/2016	Blessed Beginnings - 13828 Eastburn

This report relates only to the sample(s) as received. Test results are in compliance with the requirements of the National Environmental Laboratory Accreditation Program (NELAP) and/or one of the following certification programs:

ANAB DoD-ELAP/ISO17025 (#ADE-1542); Arkansas DEP (#88-0730/13-049-0); Florida DEP (#E87622-24); Georgia EPD (#E87622-24); Illinois DEP (#200026/003329); Kentucky DEP (AL123065/#0021); Michigan DPH (#0034); Minnesota DPH (#491715); New York ELAP (#11776/53116); North Carolina DNRE (#659); Virginia DCLS (#460153/7952); Wisconsin DNR (#999472650); USDA Soil Import Permit (#P330-14-00305).

Any qualification or narration of results, including sample acceptance requirements and test exceptions to the above referenced programs, is presented in the Statement of Data Qualifications and Project Technical Narrative sections of this report. Estimates of analytical uncertainties and certification documents for the test results contained within this report are available upon request.

If you have any questions or require further information, please do not hesitate to contact me.

Sincerely,

Gary L. Wood **Project Chemist** 

Page 1 of 11



### PROJECT TECHNICAL NARRATIVE(s)

No Project Narrative is associated with this report.

Page 2 of 11



### STATEMENT OF DATA QUALIFICATIONS

All analyses have been validated and comply with our Quality Control Program. No Qualification is required.



### **ANALYTICAL REPORT**

Client: ATC Group Services Work Order: 1607021

Project: School Drinking Water Testing Description: Blessed Beginnings - 13828 Eastburn

 Client Sample ID:
 1-BS-P-BB
 Sampled:
 06/28/16 06:10

 Lab Sample ID:
 1607021-01
 Sampled By:
 ATC

Matrix: Drinking Water Received: 06/30/16 18:30

### **Metals in Drinking Water by EPA 200 Series Methods**

Analyte	Analytical Result	RL	Action Limit	Unit	Dilution Factor	Method	Date Time Analyzed	Ву	QC Batch
Lead	<0.0010	0.0010	0.015	mg/L	1	USEPA-200.8 Rev. 5.4	07/14/16 08:20	DSC	1606894

Page 4 of 11



Page 5 of 11

### **ANALYTICAL REPORT**

Client: ATC Group Services Work Order: 1607021

Project: School Drinking Water Testing Description: Blessed Beginnings - 13828 Eastburn

 Client Sample ID:
 2-KS-P-BB
 Sampled:
 06/28/16 06:14

 Lab Sample ID:
 1607021-03
 Sampled By:
 ATC

Matrix: Drinking Water Received: 06/30/16 18:30

### Metals in Drinking Water by EPA 200 Series Methods

Analyte	Analytical Result	RL	Action Limit	Unit	Dilution Factor	Method	Date Time Analyzed	Ву	QC Batch
Lead	<0.0010	0.0010	0.015	mg/L	1	USEPA-200.8 Rev. 5.4	07/14/16 08:31	DSC	1606894



### **ANALYTICAL REPORT**

Client: ATC Group Services Work Order: 1607021

Project: School Drinking Water Testing Description: Blessed Beginnings - 13828 Eastburn

Client Sample ID: **3-US-P-BB** Sampled: 06/28/16 06:17 Lab Sample ID: **1607021-05** Sampled By: ATC

Matrix: Drinking Water Received: 06/30/16 18:30

### **Metals in Drinking Water by EPA 200 Series Methods**

Analyte	Analytical Result	RL	Action Limit	Unit	Dilution Factor	Method	Date Time Analyzed	Ву	QC Batch
Lead	0.0088	0.0010	0.015	mg/L	1	USEPA-200.8 Rev. 5.4	07/14/16 08:39	DSC	1606894

Page 6 of 11



### **QUALITY CONTROL REPORT**

### Metals in Drinking Water by EPA 200 Series Methods

	Sample	Spike			Spike	Control		RPD	
QC Type	Conc.	Qty.	Result	Unit	% Rec.	Limits	RPD	Limits	RL

Analyte:	Lead/USEPA-20	0.8 Rev. 5.4
----------	---------------	--------------

QC Batch: 1606894 (Metals Direct Analysis)						Aı	nalyzed: (	7/14/2016	By: DSC
Method Blank			<0.0010	mg/L					0.0010
Laboratory Control Sample		0.0400	0.0383	mg/L	96	85-115			0.0010
1607021-01 [1-BS-P-BB]									
Matrix Spike	< 0.0010	0.0200	0.0197	mg/L	98	70-130			0.0010
Matrix Spike Duplicate	<0.0010	0.0200	0.0203	mg/L	101	70-130	3	20	0.0010



### PRETREATMENT SUMMARY PAGE

Client: ATC Group Services

Project: School Drinking Water Testing

				Date & Time	
Pretreatment	Lab Sample ID	Batch	Ву	Prepared	
USEPA 600/R-94/173	1607021-01	1606894	JBA	07/05/16 13:36	
	1607021-03	1606894	JBA	07/05/16 13:36	
	1607021-05	1606894	JBA	07/05/16 13:36	



# **Chain of Custody Record**

COC No. 160642706

6/28/16 610 x W 6/28/16 611 x W 6/28/16 614 x W 6/28/16 616 x W 6/28/16 618 x W 6/28/16 618 x W Shipped? Hand Carrier Comments Shipped? Hand Carrier Comments Comments	Time	Rune			
6/28/16 611		2. Rating and By	6	In Marie	ATC Group Services LLC 46555 Humboldt Dr. Ste 100
6/28/16 610 x W X 6/28/16 611 x W X 6/28/16 614 x W X 6/28/16 615 x W X 6/28/16 617 x W X 6/28/16 618 x W X 1 6/28/16 618 is above detection limits, please analyze flush samples		2	Darrier		Samplier's alignature
6/28/16 610 x W X 6/28/16 611 x W X 6/28/16 614 x W X 6/28/16 616 x W X 6/28/16 618 x W X 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	If lead is above detection limits, please analyzo	Comments			Sampled By (print) Andrew Ketchum
6/28/16 610 × W X 6/28/16 611 × W X 6/28/16 614 × W X 6/28/16 616 × W X 6/28/16 618 × W X 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					10
6/28/16 610 × W X 6/28/16 611 × W X 6/28/16 614 × W X 6/28/16 615 × W X 6/28/16 618 × W X 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					
6/28/16 610 × W X 6/28/16 611 × W X 6/28/16 616 × W X 6/28/16 618 × W X 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1				The state of the s	<b>a</b>
6/28/16 610 × W X 6/28/16 611 × W X 6/28/16 616 × W X 6/28/16 618 × W X 6/28/16 618 × W X 1					8
6/28/16 610 × W X  6/28/16 611 × W X  6/28/16 614 × W X  6/28/16 616 × W X  6/28/16 618 × W X  1					7
6/28/16 610 × W X	×		6/28/16	3-US-F-BB	02 - 06 ª 3-US
6/28/16 610 × W X	٤	80792	6/28/16	3-US-P-BB	01 - 05 \$ 3-08
6/28/16 610 × W X 1 1 1 6/28/16 611 × W X 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	×	VALSE	6/28/16	2-KS-F-BB	OR - OH , 2-KS
6/28/16 610 × W X 1 6/28/16 611 × W X 1	٤		6/28/16	2-KS-P-BB	01 - 03 = 2-KS
6/28/16 610 × W X	8	0000	6/28/16	1-BS-F-BB	のス - Oえ 2 1-BS
	10.820	610	6/28/16	1-BS-P-BB	01 -0/1-1-85
Sample ID  Cooler ID  Sample Sample Sample  Number of Containers Submitted  Total Sample Comments	Matrix	7200	-	Field Sample ID C	Schodule Matrix Sample Code Number
Robert Smith Contai				atcassocia	D/D2/ Email
Invoice To Signature Comments of Signature C	ead - Pri			yan 48377	Project Chemist  Jim McFadden  Novi, Michig  Work Order No  Phone:
Client Project No. / P.O. No. (F)  188BS16284  mary (IIII)  D		o. / P.O. No. 88BS16284	Client Project No	Address 46555 Humboldt Drive Suite 100	Receipt Jos No. Address 46555 H
Project Name Blessed Beginnings - 13828 Eastburn	P)	nings - 13828 E	Project Name Blessed Begin	ATC Group Services, LLC	

# SAMPLE RECEIVING / LOG-IN CHECKLIST

*TRIMATRI	X CHOUTC - BLESSEC	BEGIN. New / Add To Work O	1601021			
LABORATORI  Recorded by (initials/date)	Cooler Cty Receive	The second secon	See Additional Cooler			
DN 6/30/16	Box Other 300	Thermometer Used Digital Thermome Other (#)	ter (#54) Information Form			
Cooler#3da Time	Cooler # Time	Cooler# Time	Cooler# Time			
Custody Seals:	Custody Seals:	Custody Seals:	Custody Seals:			
None	□ None	None	□ None			
Present / Intact	☐ Present / Intact	Present / Intact	☐ Present / Intact			
Present / Not Intact	☐ Present / Not Intact	☐ Present / Not Intact	☐ Present / Not Intact			
Coolant Type:	Coolant Type:	Coolant Type:	Coolant Type:			
☐ Loose Ice	☐ Loose Ice	☐ Loose Ice	☐ Loose Ice			
☐ Bagged Ice	Bagged Ice	☐ Bagged Ice	Bagged Ice			
Blue Ice	Blue Ice	Blue Ice	Blue Ice			
None None	□ None	□ None	Coolant Location:			
Coolant Location:	Coolant Location:	Coolant Location: Dispersed / Top / Middle / Bottom	The state of the s			
Dispersed / Top / Middle / Bottom	Dispersed / Top / Middle / Bottom	Dispersed / Top / Middle / Bottom Temp Blank Present:  Yes No	Dispersed / Top / Middle / Bottor Temp Blank Present: ☐ Yes ☐ No			
Temp Blank Present  Yes  No  f Present, Temperature Blank Location is:	Temp Blank Present: Yes No If Present, Temperature Blank Location is:	If Present, Temperature Blank Location is:	If Present, Temperature Blank Location i			
Representative Not Representative	Representative Not Representative	☐ Representative ☐ Not Representative	☐ Representative ☐ Not Representati			
		Opserved Correction	Observed Correction			
Observed Correction  *C Factor *C Actual *C	Observed Correction Actual °C	*C Factor *C Actual *C	*C Factor *C Actual *C			
Temp Blank:	Temp Blank	Temp Blank	Temp Blank			
Sample 1 24.7 0 24.7	Sample 1:	Sample 1:	Sample 1:			
Sample 2 54.4 0 244	Sample 2	Sample 2:	Sample 2			
Sample 3 24.4 0 24.4	Sample 3:	Sample 3.	Sample 3:			
345	2 Comple Assessed 2Co	2 Comple Augrana Co	3 Sample Average "C:			
3 Sample Average °C: 47.3	3 Sample Average °C:	3 Sample Average °C:				
Cooler ID on COC?	Cooler ID on COC?	Cooler ID on COC?	Cooler ID on COC?  VOC Trip Blank received?			
□ VOC Trip Blank received?	☐ VOC Trip Blank received?	☐ VOC Trip Blank received?				
	reas checked, complete Sample F	leceiving Non-Conformance and/or	r inventory Form			
Paperwork Received		Check Sample Preservation				
Yes No	march/marchiner	N/A Yes No				
Chain of Custody record(s)?	The Children of the Control of the C		nk OR average sample temperature, ≥6° C?			
Received for Lab Signed/Da	ite/Time?		was thermal preservation required? t Chemist Approval Initials:			
Shipping document?			eted Non Con Cooler - Cont Inventory Form			
COC Information		Completed Samp	le Preservation Verification Form?			
		THE RESERVE OF THE PERSON OF T	illy preserved correctly?			
COC ID Numbers: // 10/427	71	If "No", added ora				
cocid manuels. 160612	06	Received pre-pre				
		□ МеОН	□ Na <sub>2</sub> SO <sub>4</sub>			
Check COC for Accuracy		Check for Short Hold-Time Prep/A				
Yes. No	C	☐ Bacteriological	11/			
☑ Analysis Requested?		☐ Air Bags	AFTER HOURS ONLY:			
Sample ID matches COC?		☐ EnCores / Methanol Pre-Preserved	COPIES OF COC TO LAB AREA(S)			
	ches COC?	☐ Formaldehyde/Aldehyde	NONE RECEIVED			
Sample Date and Time mate Container type completed or All container types indicated	n COC7	Green-tagged containers	RECEIVED, COCs TO LAB(S)			
All container types indicated	(1555)	☐ Yellow/White-tagged 1 L ambers (SV F)	rep-Lab)			
Sample Condition Summary		Notes				
N/A Yes No	The second second					
Broken container	s/lids?					
Missing or incom	plete labels?					
O D Illegible information	on on labels?					
O D Low volume rece	lyed?		lank not listed on COC			
	non-TriMatrix containers received?	Cooler Received (Date/Time) Paperwork	Delivered (Date/Time) ≤1 Hour Goal Met			
	containers have headspace?	2N6/30/146/2	20/// Yes / No			
Extra sample loca	ations / containers not listed on COC?	CX14 4120114 616	9			



## SAMPLE PRESERVATION VERIFICATION FORM

Project Chemiss

OC 1D#/60	672/	06	Adjusted by: Date:		DO NOT ADJUST pH FOR THESE CONTAINER TYPE						
Container Type	5/23	4	13		6	15					
Tag Color	Lt. Blue	Blue	Brown		Red	Red Stripe					
Preservative	NaOH	H <sub>2</sub> SO <sub>4</sub>	H <sub>2</sub> SO <sub>4</sub>		HNO <sub>3</sub>	HNO <sub>3</sub>					
Expected pH	>12	<2	<2	T. H. III.	<2/	<2					
COC Line #1				10	1						
COC Line #2	77.53				/						
COC Line #3					1			L AL			
COC Line #4					/			-			
COC Line #5					1/	0					
COC Line #6		Valle	2011		V			C R			
COC Line #7								111			
COC Line #8	WELLS.	Time In			2.00	15					
COC Line #9											
COC Line #10	13.54(1)	100					HIE	V - 1 20			

pH Strip Reagent #				
Ø	6040263			
	AND THE REAL			

Aqueous Samples: For each sample and container type, check the box if pH is acceptable. If pH is not acceptable for any sample container, record pH in box, and note on Sample Receiving Checklist and on Sample Receiving Non-Conformance Form. If approved by Project Chemist, add acid or base to the sample to achieve the correct pH. Add up to, but do not exceed 2x the volume initially added at container prep (see table below for initial volumes used). Add orange pH tag to sample container and record information requested. Record adjusted pH on this form. Do not adjust pH for container types 6 and 15.

COC ID #		Adjusted by:		DO NOT ADJUST pH FOR THESE CONTAINER TYPES				
Container Type	5/23	4	13		6	15		
Tag Color	Lt. Blue	Blue	Brown		Red	Red Stripe		17.57
Preservative	NaOH	H <sub>2</sub> SO <sub>4</sub>	H <sub>2</sub> SO <sub>4</sub>		HNO <sub>3</sub>	HNO <sub>3</sub>		
Expected pH	>12	<2	<2		<2	<2		
COC Line #1	1	1						
COC Line #2			12.5					Einer :
COC Line #3		0 30		2544		1		
COC Line #4		1						1
COC Line #5		usari u Ele	1 22 1		13.5			S. C.
COC Line #6						- 14	111-	
COC Line #7				( K = B II		P. S. L.		HE P
COC Line #8								
COC Line #9							31 1 1 1	
COC Line #10				7				

Container Size (mL)	Original Vol. of Preservative (mL)				
Container Type 5	NaOH				
500	2.5				
1000	5.0				
Container Type 4	H <sub>2</sub> SO <sub>4</sub>				
125	0.5				
250	1.0				
500					
1000	4.0				
Container Type 13	H <sub>2</sub> SO <sub>4</sub>				
500	2.5				

500